

**GOVERNMENT OF THE DISTRICT OF COLUMBIA  
DEPARTMENT OF GENERAL SERVICES**

**DESIGN-BUILD SERVICES FOR  
ELEVEN DPR PLAYGROUNDS**

**Solicitation #:DCAM-13-CS-0106**

**Addendum No. 4  
Issued: February 12, 2013**

---

This Addendum Number 04 is issued by e-mail on February 12, 2013. Except as modified hereby, the Request for Proposals (“RFP”) remains unmodified.

**Item #1**

**Requests for Information:** Below are RFIs received and the Department’s response:

Emery

1. What is the material of the tricycle path? **Response: The tricycle path should be asphalt with painted striping.**
2. What is the material of the unstructured play zone? **Response: This area should be PIP material.**
3. What is the material for the seat walls, entrance sign, and arch sign? **Response: The materials should be masonry brick or stone with design reviewed and approved by DGS/DPR.**

Benning Park

4. Is the design intent for the dragon themed walkways to be a colored asphalt? **Response: The walkway should be a combination of colored asphalt and PIP safety surfacing.**
5. What is the surface material surrounding the raised gardens? **Response: Provide stone dust material.**

Harry Thomas

6. Is the baseball field part of the scope of work? **Response: No it is not in the scope of work.**

Harrison Playground

7. Is the existing transformer vault intended to be the power source for the proposed electrical conduit? **Response: No.**
8. What is the surface material for the music themed walkways and the music note base for the picnic tables? **Response: The material can be colored or stained concrete.**

#### Douglass Park

9. What is the size of the storage shed on concrete pad? **Response: The shed should be 10'x10' lockable shed with a concrete floor.**
10. Are we required to repair the existing bollards or provide new removable bollards? **Response: Provide new bollards. Please refer to Section F -- Site Amenities.**
11. How many interpretive signs are required? **Response: Provide (6) interpretive signs per DPR standard with design approved by DGS/DPR.**
12. Is the decomposed granite walking path an add/alt for the asphalt walking path? **Response: The base bid should be asphalt walkway.**

#### Newark Park

13. What is the size of the storage shed? **Response: The shed should be 10'x10' lockable shed with a concrete floor.**
14. What is the material of the retaining walls **Response: The design builder may recommend a material for the retaining wall with DPR/DGS approval.**

#### Banneker Park

15. What type of enclosure is required for the dumpster? **Response: Chain link fencing or similar product is acceptable which hides the dumpsters.**

#### Kennedy Rec Center

16. Is the custom play equipment "iconic symbol" included in the playground equipment budget for the park, or should it be priced separately? **Response: The "iconic symbol" play equipment is part of the allowance.**

#### Item #2

The period for questions is hereby closed.

#### Item #3

**The bid date is hereby changed.** Proposals are due by **February 19, 2013 at 2:00 pm EST.** Proposals that are hand-delivered should be delivered to the attention of: Derrick Burke, Contract Specialist, at **Frank D. Reeves Center, 2000 14<sup>th</sup> Street, NW, 8<sup>th</sup> floor, Washington, DC 20009.**

- End of Addendum No. 4 -